




Notes:

1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN WARWICK LANE DEVELOPMENTS AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.
2. WORK TO FIGURED DIMENSIONS ONLY.
3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND WARWICK LANE DEVELOPMENTS DRAWINGS AND SPECIFICATIONS.



Stainless Steel Illuminated Bollard

Height above ground: 1000mm
Depth Below Ground: 400mm
Diameter: 154mm



Air Source Heat Pumps Specifications



OUTDOOR UNIT	QUHZ-W40VA
HEAT PUMP COMBINATION	ErP Rating
HEATER - 55°C	A+
	η_{th}
	117%
	SCOP (MCS)
	2.91
HEAT PUMP COMBINATION	ErP Rating
HEATER - Large Profile ¹	A
	η_{th}
	129%
	COP
	3.00
HEATING ²	Capacity (kW)
(A-3/W55)	4.32
	Power Input (kW)
	2.18
	COP
	1.98
OPERATING AMBIENT TEMPERATURE (°C DB)	-15 ~ +35
SOUND PRESSURE LEVEL AT 1M (dB(A)) ³	43
SOUND POWER LEVEL (dB(A)) ⁴	53
WATER DATA	Pipework Size (mm)
	15
	Flow Rate (l/min)
	3 to 8
DISTANCE BETWEEN OUTDOOR	Height Difference
UNIT AND THERMAL STORE (m)	5
	Piping Length
	15
DIMENSIONS (mm)	Width
	809+705
	Depth
	300+205
	Height
	715
WEIGHT (kg)	57
ELECTRICAL DATA	Powered from indoor unit
REFRIGERANT CHARGE (kg)	Powered from indoor unit
7 CO ₂ EQUIVALENT (t)	1.15 / 0.0015

Revision Number	Revision Description	Issued by	Revision Date
STATUS: Planning Issue			



Warwick Lane.
Developments Ltd.

T 01903 233332 Ext 131 | DF 01903 206 908 | E acp@wld-group.co.uk
1 The Steyne, Worthing, West Sussex, BN11 3DS

CLIENT: Thornehead Securities LTD
10 Palm Court,
London, N16 5XA
SITE ADDRESS:
Becket Buildings,
Littlehampton Road,
Worthing, West
Sussex, BN13 1QD

DRAWING: Becket Mews West Wing
TITLE: Proposed Landscape Plan

SCALE AT A1: 1 : 100	DATE: 17/12/2024	DRAWN: UF	CHECKED: AP
PROJECT NO: WLD/001/24	DRAWING NO: WLD-001-24-08		REVISION: