**Pond Road Site Arboricultural Survey**

| Tree Number | Tree Species | Stem Diameter (mm approx.) | Height (m) | Branch Spread (m) to cardinal points | Estimated Remaining Contribution (years) | Life Stage | Observations | Category | Status | |
|---|---|---|---|---|---|---|---|---|---|---|
| 1 | Acer saccharinum (Silver Maple) | 200 Three stems, 100 One stem | 6 | 3N, 5E 4.5N 3W 3S | 40+ | Young mature | Scrubby, multistemmed tree, thin canopy | B1 | Remove To accommodate Development | |
| 2 | Prunus Pissardii (Purple Plum) | 400 | 6 | 4NSE, 3W | 15 | mature | Good condition, leans to NW AT 60 deg | B1 | Remove To accommodate Development | |
| 3 | Acer platanoides Scwedleri (Norway Maple) | 450 | 10 | 5NSE 4W | 30+ | mature | Good condition, crown recovering from leaf scorch | B1 | Remove To accommodate Development | |
| 4 | Prunus Pissardii (Purple Plum) | 300 | 6 | 4NSW 3E | 15 | mature | Good condition | B1 | Remove To accommodate Development | |
| 5 | Prunus Kanzan (Japanese Cherry) | 350 | 7 | 4NSE, 32W | 15 | mature | Fair condition, one sided crown | C1 | Remove To accommodate Development | |
| 6 | x Cupressocyparis leylandii sp. | 600 | 9 | 5 | 30 | mature | Dieback in crown, dead wood, poor form | C2 | Remove and replace in new landscape proposals | |
| 7 | x Cupressocyparis leylandii sp. | 600 | 10 | 5 | 30 | mature | as above and low branches over highway | C2 | Remove and replace in new landscape proposals | |
| 8 | x Cupressocyparis leylandii sp. | 700 | 11 | 7 | 30 | mature | as above and low branches over highway | C2 | Remove and replace in new landscape proposals | |
| 9 | Betula pendula (Silver Birch) | 150 | 9 | 4 | <10 | mature | Suppressed small tree, very poor crown with dieback and dead wood | R | Remove and replace in new landscape proposals | |
| 10 | Betula pendula (Silver Birch) | 150 and 100 | 7.5 | 3 | 20 | mature | Twin stem, small low crowned tree | B2 | Remove and replace in new landscape proposals | |
| 11 | Sorbus aria (Whitebeam) | 250 | 6 | 3 | 30 | young mature | Good form and condition | B1 | Retain | |
| 12 | Aesculus hippocastanum (Horse Chestnut) | 150 | 5 | 3 | 5 | Young | Bleeding Canker (Pseudomonas syringae pv | R | Remove and replace in new landscape proposals | |
| 13 | Cuppressus lawsoniana (Lawson Cypress) | 400 | 10 | 3 | 30 | Young mature | Thin crown with some dieback | C1 | Retain | |
| 14 | Prunus Kanzan (Japanese Cherry) | 400 | 9 | 5 | 20 | mature | One sided crown to east, ivy clad, poor form | C1 | Retain | |
| 15 | Sorbus aria (Whitebeam) | 300 | 8 | 3.5 | 30 | Young mature | Good form and condition | B1 | Retain | |
| 16 | Sorbus aucuparia (Rowan) | 300 | 7 | 3 | 0 | Young mature | Dead/dying | R | Remove | |
| 17 | Fraxinus excelsior (Common Ash) | 350 | 8 | 4 | >50 | Young mature | Good form and condition | B1 | Retain | |
| 18 | Crataegus prunifolia (Plum Leafed Thorn) | 250 | 6 | 3 | 20 | mature | Good form and condition | B1 | Retain | |
| 19 | Fraxinus excelsior (Common Ash) | 200 | 7 | 4 | 50 | Young mature | Twin stem arising from 1m at weak fork | C1 | Retain | |

ADUR & WORTHING
PLANNING SERVICES
PLAN AWDM/1041/13
DATE VALID 212 AUG 2013