TASKS		JANUARY	FEBRUARY	MARCH	APRIL	MAY	JUNE	JULY	AUGUST	SEPTEMBER	OCTOBER	NOVEMBER	DECEMBER
NATIVE HEDGEROWS	Main prune/cut back hedgerow to desired height												
	Clear any lateral branches encroaching onto pathways												
	Check for damaged or diseases species and remove/replace												
	Top up bark mulch around the base of hedgerow and clear weeds												
	Ensure hedgerow species are adequately watered during warmer weather												
TREES	Prune - remove any dead, diseased, crossing or damaged branches.												
	Check tree stakes and ties for damage and positioning												
	Rake up and remove leaves												
	Ensure trees are adequately watered during warmer weather												
	Check for pests and diseases and treat as required												
	Top up bark mulch around the base of trees and clear weeds												
WILDFLOWER AREAS	Water vegetation mats through the first spring/summer growing season												
	Mow during the first year every 6-8 weeks during Summer to a height of 5cm												
	Annual 'Hay Cut' using a strimmer or scythe to a height of 50mm. Leave arrisings for a week before clearing to allow seeds to drop. Check area for wildlife prior to cutting												
	Spring cut to 7.5cm using a mower or strimmer. Clear arisings												
	Remove weeds by hand. Clear any rubbish/unwated material blown into beds												
HERBACEOUS PERENNIALS	Lift and divide large clumps if necessary												
	Clear old growth and cut back												
	Clear weeds from beds												
	Deadhead plants for a second flowering if required												
	Water during establishment and thereafter in hotter weather and times of drought												
	Replenish planting by cutting back dead growth if desired												
	Main perennial cutback. Leave evergreens and grasses to provide winter interest												
SHRUBS AND GROUNDCOVERS	Water during establishment and thereafter in hotter weather and times of drought												
	Spring pruning for July-October flowering plants												
	Summer Pruning for shrubs that flower in late winter, spring and early summer												
	Evergreen shrub pruning												
	Light pruning for newly planted shrubs during the first 1-2 years growth												
	Top up mulch in shrub beds as required												
GENERAL	Adjust irrigation according to season												

LEGEND:

GENERAL NOTES.

This drawing remains the copyright of kold studios Limited.
Any context outside site boundary is indicative only.
Drawing to be read in colour.
All dimensions in millimetres.
All dimensions indicative only.
All dimensions must be checked on site and any discrepancies verified with the landscape architect.
Drawing based on survey information by others.
Drawing to be read with all other issued information.
Refer architect's information for all architectural elements.
All footings, foundations & structural elements to engineer's design & specification
Refer to engineer's information for all engineering elements.
Any discrepancies between the drawings and site conditions be brought to the attention of the contract administrator and/or landscape architect for review.

issue	date	issue purpose	notes	drawn	checked
1	251229	PLANNING		KG	--

kold
landscape architecture | garden design
T: +44 (0) 07925924735 | info@koldstudios.co.uk
6 marlborough place, brighton, bn1 1ub

project no.	drawing no.	issue.
010	0030-KOLD-GF-SH-L-700	1

client: Alex Coombes

project: Ambrose Place
Worthing

drawing: Incdicative Maintenance Schedule

scale: na