JM

T.P. OFFICE COPY

REVISED PLAN

BOROUGH COUNCIL WORTHING
DEPOSITED 15-01-08
WARD NO.
WB/ 07 / 1233 / FULL

WORTHING BOROUGH COUN
21 JAN 2008
CONSENT GRANTED
SUBJECT TO CONDITIONS

REPAIR EXG. DAMAGED FAI. & PROTECT WITH NEW GALVANISED HOOPS FIXED TO WALL

SHORT SECTION OF METAL RAILING

750

215 THICK FACE BRICK WALLS WITH BRICK PIERS @ 2000 HIGH

CONC. RAMP

TIMBER DOORS

2200

RETAIN EXG. CONC. KERBS

bins enclosure

(EXG. CONC. FLOOR TO REMAIN)

4920

2720

280

280

6670

280

Plan as proposed.

BLACK PAINTED VERTICAL METAL RAILINGS

FILL IN EXG. OPENING TO CAR PARK WITH HARDWOOD DIAG. BOARDING WITH 20mm. GAPS ON HARDWOOD FRAMING. TO 2M. HIGH

BOE & TILE CREASING.

FACE BWK. TO MATCH EXG.

2M

West.
Elevations as proposed.

South.

DOORS:
PAIR OF HARDWOOD VERT. BOARDED WITH 20mm GAPS, HARDWOOD FRAMES & BRACES.
IRONMONGERY:
GALVANISED HASP & STAPLE HINGES, ONE LEAF WITH UNTERNAL GALV. SHOOT BOLT, 1 LEAF WITH SUITABLE LOCK.

150 X 150 HARDWOOD POSTS FIXED TO WALLS

2180

East.

FAI

hardstanding for bins.

← CONC. FLOOR WITH RAISED RC. EDGING →

Plan as exg.

West.
Elevations as exg.

South.

East.

A TH 13.1.08 DWG. REVISED TO SUIT PLANNING DEPT

Stoke Abbott Court, WORTHING.

proposed bins enclosure.

drawn	scale	job	dwg	
TH	1:50	444	02	A
date 4.11.07				

B.A. HUGHES
162 Ladysmith Road,
Brighton,
East Sussex BN2 4EF
01273 689930
07703 255626

James P. Maginnis Ltd