Woodsmen Tree Services
137 North Bersted Street
Bognor Regis
West Sussex
PO22 9AG

Dr Gavin Walker
07840 816716
01243 278591
woodsmentreeservices@gmail.com

www.woodsmentreeservices.co.uk

TREE REPORT

Client Contact Details: [redacted] [redacted] Mob: [redacted] Email: [redacted]	Date Report Sent: 29th August 2024 Ref Number: 1222 Surveyor: Dr Gavin Walker

TPO TREE WORKS

T1. SYCAMORE MAPLE TREE *(Acer pseudoplatanus):* This large specimen tree is appearing to grow well and is now in need of sympathetic arboriculture to regain a more manageable and appropriate size for the location. It is also now encroaching on the adjacent public road. Furthermore, there is evidence of a major pollard a number of years previously which has taken time for the tree to recover from. It is worth noting that a re-pollard is not recommended. The following sympathetic tree surgery is recommended:

- A 25-30% crown reduction.
- The asymmetric width is to be reduced from c.25m by 5m (2.5m each side) leaving a span of 20m.
- The height is also to be reduced by approximately 5-7m from 25m leaving a height of 20m.
- The crown is to be lifted to enable high sided vehicles to pass under the tree unhindered. A crown lift up to 5m from ground level is suggested.
- Removal of significant deadwood.

Additional Notes:

- *All work is undertaken by fully trained NPTC professionals. Public Liability & Employer's Liability insurance is provided up to £5 million.*
- *Our trained arborists will ensure that all cuts made are clean and to high arboricultural standards and complying with BS3998:2010.*
- *All waste is to be disposed of at Stubbs Copse Woodyard near Arundel. Clear up all arisings and leave the site clean from all debris.*