Mature *Cupressus macrocarpa* - dead wood / hanging branches to be removed by appropriately qualified tree surgeon.

PA: 01

PA: 02

PA: 03

PA: 04

PA: 05

EPA: 06

EPA: 08

PA: 07

EPA: 09

EPA: 10

EPA: 11

EPA: 12

PA 13
2 no existing conifer trees to be removed and replaced

PA: 14

Grass Turfed Area

Grass Turfed Area

Area adjacent to building to have permeable geo-textile overlain with 'Scottish Pebbles'

PA: 15

PA: 16

PA: 17

PA: 18

Existing Cedar Conifer to be retained

10m

25m

N

KEY

Existing Trees
Existing trees to be retained and protected within the proposed development scheme.

Existing Conifers Proposed to be Removed
Existing low grade conifers trees proposed to be removed.

Proposed Tree Planting
Proposed native species tree specimens to be 12-14 cm Girth Size / 3.5-4.25m height / 1.75-2.0m Clear Stem / Standard Heavy Stock. Trees to be supplied and planted in accordance with *BS 8545: 2014 Trees: from nursery to independence in the landscape: Recommendations.*

Proposed Hedgerow Planting
Proposed hedgerow planting areas to be 300mm depth (minimum) subsoil overlain with 450mm (minimum) multi purpose topsoil to *BS3882: 2015 'Specification for Topsoil'*. Hedgerow planting areas to have 75 mm (min) depth of ornamental bark mulch.

Proposed Ornamental Shrub Planting Areas
Proposed ornamental shrub planting areas to have 300mm depth (minimum) subsoil overlain with 450mm (minimum) multi purpose topsoil to *BS3882: 2015 'Specification for Topsoil'*. Shrub planting areas to have 75 mm (min) depth of ornamental bark mulch.

Existing Ornamental Shrub Planting Areas
Existing ornamental shrub planting areas to be reinforced with additional planting. Soil within existing planting areas is to be lightly forked over taking care not to disturb existing shrubs/roots all planting areas to have 75 mm (min) depth of ornamental bark mulch.

Proposed Grass Seeded/Turfed Areas
Proposed grass seeded/turfed areas to have 300mm depth (minimum) subsoil overlain with 150mm (minimum) multi purpose topsoil to *BS3882: 2015 'Specification for Topsoil'*

Proposed Ornamental Loose Stone
Proposed 'Scottish Pebbles' to be laid over permeable geo-textile.

NOTES
Refer to
- *RCo203/ 02 / Planting Layout*;
- *RCo203/ 03 / Planting Layout*;
- *RCo203/ 04 / Planting Layout*;
- *RCo203 / Detailed Plant Schedule and Specification*

for detailed planting proposals

REV	DESCRIPTION	DATE	INITIALS
01	Layout updated following comments	08-05-17	AR

Ramsay & Co
Landscape Architecture

The Studio, 68 Cuckfield Road, Hurstpierpoint, West Sussex, BN6 9SB
T: 01273 834 198 M: 07973 770047 E: landscape@ramsayandco.com

Project Title:
Southlands Hospital, Shoreham-by-Sea
Crowther Architects Associates

Drawing Title:
Planting Layout

Scale:	*Drawn:*	*Date:*
1:250@A1	AR	18-04-17

Drawing Number: RCo 203 / 01

Revision: 01