

External Material Schedule- Rev B- Office Block in Westholme Clinic

	MATERIAL SCHEDULE	
1	Brickwork Match to existing West Hoathley Medium Multi (discontinued). Equivalent closest available alternative to be selected, such as Chailey Medium Multi Stock	
2	Bay below window openings to be finished in either white weatherboard cladding match to existing or white brickwork /White painted brickwork	
3	Windows /External Door Either powder-coated white aluminum double glazed casement windows windows (white – RAL Colour tbc.) trickle vents in staff wing Full height glazing and associated doors – Aluminum	
4	Render Weatherby's white render	
5	Parapet Roof powder coated (grey) aluminum parapet capping	
6	Canopy Over Main Entrance White/ Grey Powder Coated Steel Frame Canopy, Crystal Clear Acrylic Glazing	
7	External Hard Surfaces Marshal Paving Slab range for paths and patios/ Colour & Size TBC	