21 John Street
Shoreham BN43 5DL
Phone: 01273 273 163

RE-RENDERING

Please see below summary of re-rendering to fulfil your point 4 request.

Re-rendering Process - all materials consistent with existing render to rear modern extension constructed circa 1997 (see spec below)

Remove unsound render and chop back surrounding render to sound base
Clean all surfaces
Application of Sand finish base coat with appropriate sand-cement mix to approx 15mm
Application of Sand finish top coat with appropriate sand-cement mix to approx 5mm
Reinstate ashlar lines
Paint with matching exterior masonry paint, 2 coat

