AMENDMENT

Existing /

Existing Wall

Plan On Gate

Hinge to detail

ADUR & WORTHING PLANNING SERVICES	
PLAN	NOTICE/0008/17
DATE VALID	Dec 18/1/17

3500

15 1725 20 1725 15

50 x 50 x 5 SHS

60 x 5 flat drilled 8Ø

Slide bolt and locking tab to take padlock

50 x 5 flat tie

95 x 18 T & G boarding bolted to 60 x 5 flat with 6Ø dome head galv bolts

150 x 150 x 5 SHS

1200

150 x 150 x 5 SHS

60 x 5 flat drilled 8Ø

50 x 50 x 5 SHS

90

Drop bolts

700

Elevation On Inside of Gate

Rev.	Revision	Drawn.	Date.
A	Scale ammended to 1:10 @ A3	sl	18.07.17

Drawn. SLDS	Date. 22.06.17	Scale. 1:10 @ A3	
Project. New Gate - Shoreham B & M McHugh Ltd		Title. Gate Arrangement	
		Drg No. 101953 / 01	Rev. A

The S.L.D.S. Partnership
6 Otter Close, Bishopstoke
Eastleigh, Hampshire. SO50 8NF
Tel 023 8069 4701
Fax 0560 314 3447
email: steve@slds.co.uk

Finish. Galvanised & PPC
All weld are 6mm Fillet weld full profile unless noted otherwise.
Third Angle Projection