Brief Specification To The Roof Repairs On Worthing Baptist Church - South Side Main Pitched Roof

Preliminary & Enabling Works

Supply, erect & maintain suitable scaffolding to facilitate the works

Provide welfare facilities for use by operatives throughout the works

Supply Heras fencing to form site compound

Supply skips for removal of waste to licensed facilities

Roofing Works

Strip & dispose of existing pitched slope roof (slate, batten, felt)

Strip & dispose of existing lead box gutter & lead flashings

Supply & install Cromar VENT 3 Air permeable membrane

Supply & install 25x50mm treated graded batten

Supply & install 24” x 12” Spanish slates

Supply & install Slate hooks

Supply & install Marley 450mm ridge tiles – slate black (to match roof pitch)

Supply & install Code 6 lead box gutter

Supply & install Building paper underlay

Supply & install Code 5 150mm lead flashings (step flashing on pitched slope & cover flashing In the box gutter)

Additional Costs

Include a quote for box gutter amendments (OSB renewal)