LEGEND

- Red Brick Paved Footway to be taken up and removed to Tip (1,664m²)
- Red Brick Paved Footway to be taken up palitised ar taken to store 900m2. Set aside 40m2 for re-use (Paving Type RP)
- Block Paved Footway to be taken up and removed to Tip (30m²)
- Block Paving (Dark Grey) to be taken up and removed to Tip (106m²)
- Modular Paved Footway to be re-laid (131m²)
- Modular Paved Footway to be taken up and set asid for re-use (50m2) Excess to tip off site
- Tactile Paving to be taken up and removed to tip off site (25m²)
- Verge to be taken up and removed to tip off site (255m²)
- Compass Paving to be taken up and removed to Client's Store (40m²)
- Timber deck to be taken up and removed to tip off site (30m²)
- Granite kerbs to be taken up and set aside for re-use (321m²)
- Natural stone kerbs to be taken up and set aside for re-use (60m²)
- Channel kerbs to be taken up and removed to tip off site (21m²)
- Brick edge kerb to be taken up and removed to tip off site (72m²)
- Guardrail to be taken down and removed to tip off site (21m²)

NOTES

1. Telent are required to disconnect the existing signal controller. The Contractor will be responsible for all other works.
2. Enerveo will be required to disconnect all existing lighting columns. The Contractor shall be responsible for all other works.

Existing Traffic Signals 'Telent' are required to disconnect decommission the existing signal controller. The Contractor will be responsible for removal and safe disposal of all equipment

SITE CLEARANCE LIST

REF NO	DESCRIPTION	QUANTITY (ea.)	ACTION
001	Road Sign	5	Take down existing sign including post and remove to tip off site
002	Road Sign	4	Take down existing sign and remove to tip off site
003	Timber Bench	3	Take up timber benches and remove to tip off site
004	Dining Seat	5	Take up existing dining seats and remove to tip off site
005	Concrete Bench	6	Take up concrete bench and remove to tip off site
006	Cycle Stands	3	Take up cycle stands and remove to tip off site
007	Bins	3	Take up bins and remove to tip off site
008	BT Phone Box	1	BT Phone Box taken down adn removed by others
009	Drop down bollard	4	Take up drop down bollards and remove to tip off site
010	Traffic Signal	4	Take down Traffic Signals and remove to tip
011	Timber Planter	11	Take up timber planters and remove to tip off site
012	Lighting Column	4	Take down lighting columns and remove to tip
013	Landscape Feature	2	Take up landscape features and remove to tip off site
014	Marker Stone	1	Take up Marker Stone and remove to tip off site
015	Canopy with columns	4	Take up canopies including columns and remove to tip off site
016	Royal Mail Post Box	1	RM Post Box to be taken down and delivered to RM store
017	Bollard	18	Take up bollard and remove to tip off site
018	Timber Bench	7	Take up bollard and remove to tip off site
019	Cycle Stand	16	Take up cycle stands and remove to tip off site
020	Cycle Stand	7	Take up cycle stands and remove to tip off site
021	Tree	3	Take up trees and remove to tip off site
022	Gully cover and frame	17	Take up gully cover and frame and tip off site

Rev	Date	Description	Drn	Chk	App
0	06.05.25	CONSTRUCTION ISSUE	IC	DP	GW

This drawing has been specifically prepared to meet the requirements of the named client and may contain design and innovative features which differ from conventional design standards.

PROJECT CENTRE

www.marstonholdings.co.uk/projectcentre

Client: WORTHING BOROUGH COUNCIL

Project: MONTAGUE PLACE

Drawing Title: SITE CLEARANCE

Drawing Status: CONSTRUCTION

Drawn	Designed	Date	Scale	Size
GS	GS	SEPT 24	1:250	A1

Drawing No.: 1000007856-5-0200-01

Rev: 0

G:\Project Centre Brighton\Brighton\Project-BST\1000007856 AWV Montague Place RIBA 2-4\2 Project Delivery\6 CAD\2 Drawing\7 CONSTRUCTION\1000007856-5-0200-01 - SITE CLEARANCE.dwg