CHESTERFIELD ROAD

ATCN

AREA IN ABEYANCE, ADDITIONAL TOPOGRAPHIC SURVEY INFORMATION REQUIRED TO COMPLETE DESIGN

Refuse can't make a turn at this point.

Communal bin collection distance = 9m. WSCC to confirm acceptability.

Communal bin collection distance = 11m. WSCC to confirm acceptability.

Communal bin collection distance = 10m. WSCC to confirm acceptability.

Communal bin collection distance = 6m. WSCC to confirm acceptability.

Communal bin collection distance = 17m. WSCC to confirm acceptability.

Bin collection point distance = 15m. WSCC to confirm acceptability.

AREA IN ABEYANCE, ADDITIONAL TOPOGRAPHIC SURVEY INFORMATION REQUIRED TO COMPLETE DESIGN

MP 12.25

ROAD 1 ROAD 2 ROAD 3 ROAD 3.1 ROAD 3.2 ROAD 4 ROAD 5

BARRINGTON ROAD

Maltby Survey Ltd- Additional Topo Information

0 5 10 20 30 40 50m

1 : 500

LEGEND


5m Communal bin collection Radius circle.

25m Collection Radius from refuse vehicle.

Area of Concern

NOTE THAT COMMUNAL BIN COLLECTION IS USUALLY 5m

Refuse Vehicle Profile



Phoenix 2 One-Pass (with Elite 6x4 chassis)

Overall Length	11.180m
Overall Width	2.550m
Min Body Height	3.360m
Min Body Ground Clearance	0.312m
Track Width	2.550m
Lock to lock time	4.00s
Kerb to Kerb Turning Radius	10.150m

General Notes

1. Where this drawing has been issued in electronic .dwg format it has been done so in good faith. ATCN Consulting LTD do not take any responsibility for any inaccuracies in the electronic data, which should be checked against the paper (or .pdf) drawing issue. Any apparent discrepancies should be immediately reported to ATCN Consulting LTD. The electronic .dwg file should not be assumed to be to scale and should not be used for 'overlaying', setting out or checking of any third party information. All dimensions should be taken from the paper (or .pdf) version of the drawing. Electronic drawings may contain third party information. ATCN Consulting LTD take no responsibility for this information, which should be checked against the originators paper drawing(s).
2. All dimensions to be checked on site prior to construction/fabrication.
3. Do not scale from this drawing.
4. Any discrepancies between drawings of different scales, and between drawings and specification where appropriate to be notified to ATCN Consulting LTD for decision.
5. Copyright reserved. This drawing may only be used for The Client and location specified in the title block. It may not be copied or disclosed to any third party without the prior written consent of ATCN Consulting LTD.
6. This drawing should only be used for construction if the drawing status is "Construction". ATCN Consulting LTD take no responsibility for construction works undertaken to drawings which are not marked with this status.

Health & Safety Note

The details on this drawing have been prepared on the assumption that a competent contractor will be carrying out the works. If the contractor(s) considers that there is insufficient Health and Safety information on this drawing, this should immediately be brought to the attention of the designer.

HAZARD IDENTIFICATION BOX

This table is provided to assist the Principal Contractor to fulfil their obligations under the CDM Regulations 2015

Hazard Ref	Hazard Type (Construction/Maintenance/ Cleaning/Demolition/Adaptation)	Hazard Description	Mitigation Measures/ Residual Risk
1	ALL	Working adjacent to Rail Track	Contractor to install necessary barriers and exclusion zones.
2	ALL	Working adjacent to live carriageway	Contractor to install necessary traffic management.
3	ALL	Working with deep excavation	Safety MS, fencing/signing, correct shoring & propping of excavation
4	ALL	Working near by steep banking	Contractors Safety method statement. Fencing, guarding and signage.
5	ALL	Live utilities including GAS/ELEC/WATER	Contractors Safety Method Statement. Scan / Locate and mark all services prior to commencing work. Hand dig to locate services
6	ALL	Potential/localized petroleum hydrocarbon BTEX,VOC and PCB	Contractor to provide relevant PPE to workers, and hotspots marked out onsite.
Site Wide	ALL	Potential ground gases and elevated arsenic	Contractor to provide relevant PPE to workers, and hotspots marked out onsite.

Rev.	Date	Description	Drn / Chk'd / App'd
C2	21/12/23	Approved for Construction	KA/MS/AA
C1	17/03/2023	Construction Issue - Subject to approve	MS/KM/AA
T1	10/02/2023	Tender Issue	KA/KM/AA
P1	14/09/22	Preliminary Issue	KM/AA/AA

Suitability: A1 - Approved/Stage Complete

Client Logo: Bellway

ATCN CONSULTING
Civil & Structural Engineers
Suite - 45D, Isabel House, 46 Victoria Road, Surbiton, KT6 4JL.
Web: www.atcnconsulting.com
Tel: 02083901377

Client: Bellway Homes LTD

Job: Barrington Road, Durrington

Title: Refuse Collection Plan

Classification: FI_60_20

Scale @ A1: 1: 500

Certified ISO 14001:2015 Environmental Management

Certified ISO 9001:2015 Quality Management

Project - Originator - Volume/System - Level/Location - Type - Discipline - Number: K43058-ATCN-XX-ZZ-DR-Z-7003

Revision: C2

Document/Drawing Number

ATCN Consulting Ltd. 2023 ATCN Internal Project Number: K43058

ATCN Ref: 020319 Rev E

Compiled to BS7000:2001