SPECIALIST ROOFING SERVICES

AWDM/0840/14

IMPERIAL CONTRACTS

ADUR & WORTHING
27 JUN 2014
PLANNING SERVICES

Sarah Crease - Planning Technician
Adur & Worthing Councils
Planning Services
Portland House
44 Richmond Road
Worthing
West Sussex
BN11 1HS

24th June 2104

Dear Sarah

Ref: Old Scantlings, 26 Church Street, Shoreham-by-Sea, West Sussex

On behalf of Mrs Williams, I attached a Site location Plan as per your request in your letter dated 20th June 2014. I have highlighted Mrs William's property for your reference.

As part of your request, I attach images of the proposed works location, which only relates to the front elevation parapet gutter lining as proposed using Kemper waterproofing.

The current lead weathering is excessively oversized which is causing the existing lead to fail due to splits. As I have previously explained, to adjust the substrate to accommodate new lead will mean an enormous amount of timberworks and increased steps in the parapet gutter. I envisage in accordance with the Lead Sheet Association's guidelines this gutter will increase on top section to within 200mm of the top of the parapet wall. The gutter sole will be a significantly wider girth to around 1200mm meaning we will require wood rolls down the middle of the gutter bays.

I can confirm that the proposal of using the Kemper waterproofing only relates to the front elevation parapet gutter linings, and nowhere else on this property.

If you require further information, please do not hesitate to contact me.

Yours sincerely

[redacted]

Peter Lane

ADUR & WORTHING
PLANNING SERVICES

PLAN	AWDM/0840/14
DATE VALID	19 JUN 2014

Imperial Contracting Limited
T/A Imperial Contracts
Staplefields Cottage, Horsham Road, Steyning,
West Sussex, BN44 3AA
tel: 01903 815812 fax: 01903 815773
www.imperialcontracts.co.uk

NFRC National Federation of Roofing Contractors
CHAS Accredited Contractor
FTMRC
Company registered in England No. 4324907