# Uridge Tree Surgeons

52A Middle Road, Shoreham By Sea, West Sussex, BN43 6GA.
Telephone: 01273 239743
Email Uridge@ntlworld.com

Tuesday, 05 July 2016

**Name:** Romans Care Home

**Property Address:** 1 Roman Road
Southwick
West Sussex
BN42 4TP

Tel: [redacted]

**Job Location & description:**

**Tree works for tree Survey April 2016**
**Located on site plan**

| | | |
|---|---|---|
| **T1.** | **Sycamore.** | Remove all major dead wood. |
| **T2.** | **Sycamore.** | Remove as close to ground level as possible and replant new tree. |
| **T3.** | **Holm Oak.** | Reduce branches to north 2m,lift crown 3m, sever ivy approximately 1m from base. |
| **T4.** | **Laurel.** | Remove all major dead wood. |
| **T5.** | **Holm Oak.** | Reduce branches to north 2m,lift crown 3m. |
| **T6.** | **Sycamore.** | Sever ivy 1m from base. |
| **T7.** | **Cherry.** | Remove 1x rubbing limb from middle of the crown. |
| **T8.** | **Holm Oak.** | Supply and Install dynamic tree support system. |
| **T10.** | **Holm Oak.** | Remove broken limb over pavement sever ivy. |
| **T11.** | **Holy.** | Sever ivy lift crown over pavement. |
| **T12.** | **Purple plumb .** | Sever ivy. |
| **T13.** | **Cherry.** | Remove as close to ground level as possible. |
| **T15** | **Beech.** | Supply and Install dynamic tree support system. |
| **T18** | **Lime.** | Sever ivy 1m from base as much as possible. |

ADUR & WORTHING
PLANNING SERVICES

| | |
|---|---|
| PLAN | AWDM/ 1039/16 |
| DATE VALID | - 7 JUL 2016 |

Yours faithfully,

Chris Uridge

N.A.A. Member ID: 60642
(All Works to BS3998)

MEMBER
NATIONAL ARBORIST ASSOCIATION

This estimate is valid for 3 months

N. P. T. C. Qualified  Fully Insured

*We always maintain a safe and tidy site!*