DFG/408/0037/4/A

HOUSING GRANTS, CONSTRUCTION & REGENERATION ACT, 1996

DISABLED FACILITIES GRANT

Address of Property : 30 Penstone Close, Lancing

SCHEDULE OF WORKS

		£
1.0	HARDSTANDING TO FRONT OF PROPERTY	
1.1	A hardstanding is to be constructed at the front of the existing property, adjacent to the garage and entrance porch. Hardstanding to be 3600mm wide x 4800mm in length, in addition a 900mm wide path is to be formed between the hardstanding and the garage side wall. Hardstanding is to be extended at 45 degrees to meet the existing concrete parking area to the front of the garage.	
1.2	The hardstanding is to be constructed using concrete or tarmacadam and is to have a slip-resistant surface finish. The contractor is to provide details of proposed materials within his estimate and a sketch plan to indicate the location of the hardstanding.	
1.3	Hardstanding is to be as level as possible, but allowing sufficient falls in order to discharge surface water.	
	TOTAL :	

NOTES:

1. All works carried out under an approved grant should comply with the requirements of this Schedule. Any queries that arise should be referred to this authority, for clarification, prior to works being carried out.

2. A copy of this Schedule is to be priced by the contractor and attached to his estimate.

G Cushing

.....

Environmental Health Officer
Please ask for N. Dell, Building Surveyor,
(Environmental Health)

10.4.2012

.....

Date of Inspection

AD[illegible]IG PLA[illegible]ES	
PLAN	AWDM/1129/12
DATE VALID	17 SEP 2012

Hsg/Schedules/30 Penstone Close