

Works are part of a maintenance program to be started over the course of this year. Work would help maintain the health and safety of the site, clearing pathways and carriageways, clearing from buildings etc.

Works would not be detrimental nor affect amenity values of the trees or area.

Section 5, Leyland Cypress: At present there is approximately 1.8m ground clearance. Would be removing the low stems leaning towards the carpark. Removing these would give 4 to 4.5m clearance.

Section 9, Holm Oak & Copper Beach: At present there is approximately 1 to 1.5m clearance from the building on the Holm Oak. Would be reducing the lower crown on the Western aspect by 1 to 1.5m, depending on growth point options to reach the minimum clearance of 2m. Clearance over path is at 2m at lowest point and 3m over highway at lowest point. Would be crown lifting over path by 1m and over highway by 2.5m to gain the required clearance.

At present there is approximately 0.5m clearance from the building on the Copper Beach. Would be reducing the lower crown on the NW aspect 1.5m, depending on growth point options to reach the minimum clearance of 2m.

Section 11, Sycamore: At present, the tree is touching buildings. Would be reducing the lower/mid crown on the NW and SE by 1 to 1.5m to reach the required clearance.

