Hyland Edgar Driver
Landscape Architects
& Urban Designers

Winchester: One Wessex Way, Colden Common, Winchester
SO21 1WG
Tel: 01962 711 600 Fax: 01962 713 945

HED.1520.Centenary House, West Durrington
29 Nov 2023

Will McKay
Development Manager
Suite B, Broadmede House,
Farnham Business Park
Farnham GU9 8QT

Dear Will

Centenary House, West Durrington
Replacement Tree Planting

We confirm that 10 trees and 1 group of trees have been identified for removal, of which 5 are category B with the remaining all category C, at the above project to accommodate the proposed vehicular entrance as detailed with the Arboricultural Development Statement:

To mitigate this loss, 7 trees will be proposed along the frontage aligning Littlehampton Rd to the following specification:

- 5no Common Sycamore at 16-18cm girth
- 2no Atlas Cedar at 16-18cm girth.

The species have been selected to enhance the existing woodland mix along this boundary in an arrangement that will provide more suitable growing conditions than currently present with the removal area.

All specimens will be planted as Advanced Heavy Standard specimens with Sycamores positioned at 5m intervals and Atlas Cedars at 10m intervals to enable suitable growing conditions for each tree. As such, the proposal maximises the planting along the frontage aligning Littlehampton Rd – due to the constraints of that area and the specimen requirements it is not physically possible to plant any further additional trees.

It should also be noted that the loss of the existing 5 higher quality category B tree specimens will be fully compensated for as part of the proposal.

It is considered that the selected species and size are appropriate substitutions for location, environment, and purpose.

Yours faithfully,

Joanna Waterfield
On behalf of Hyland Edgar Driver

Encl.
Cc Will Mckay