NOTES

N.B. All planting needs to be carried out only between October and February.

1. Please refer to specification when implementing this design.
2. Topsoil for all plant beds should be a minimum of 400mm. Ensure all rubble and rubbish is removed and the full 400mm depth of the empty plant beds is noted by the supervisor before placing topsoil. All plant composts are to be peat-free. Glyphosate weedkiller only is approved for use.
3. Slow release fertiliser shall be added to each plant pit at a rate of 35g per plant and 200g per tree.
4. All plants shall comply with the Horticultural Trades Association National Plant Specification.
5. All plants and trees should be thoroughly watered in after planting, soaking to full depth of soil.
6. Well composted wood chip mulch should be applied to all planted areas at a rate of 75mm settled depth after thorough watering or heavy rain.
7. Maintenance: Planting should be maintained with forking out weeds, regular watering in dry weather for first two years, checking and loosening tree ties as necessary with removal after two years and removal of rubbish and litter. Mulch should be topped up to 75mm settled depth annually and fertiliser added one year after planting.Maintenance shall be for five years during which time the contractor will be liable for plant losses which occur due to death , disease or deformity and vandalism before practical completion. All plants lost shall be replaced in the first three years with gaps filled in the fourth and fifth years after planting.

N.B. All waste material arising from the planting and maintenance work shall be removed from the site at each visit.



Scientific Name	Common Name	Size	Number	Specification
Shrubs				
Amelanchier canadensis	Snowy Mespilus	7lt	2	
Cistus 'Silver Pink'	Rock Rose	2lt	19	
Cotoneaster franchetii	Cotoneaster	7lt	2	
Deutzia 'Rosalind'	Deutzia	2lt		
Escallonia rubra 'Woodside'	Eleagnus	2lt	35	
Hebe 'Gauntlettii'	Hebe	2lt	36	
Lavandula 'Hidcote'	Lavender	2lt	26	
Pittosporum tenuifolium	Pittosporum	7lt	27	
Potentilla Sunset	Potentilla	2lt	2	
Potentilla recta 'Warrenii'	Potentilla	2lt	8	
Phlomis italica	Italian Sage	2lt	23	
Stephanandra incisa cnispa	Stephanandra	2lt	3	
Viburnum davidii	Dwarf viburnum	2lt		
Viburnum tinus	Laurustinus	7lt		

All plants to conform to the Horticultural Trades association Specification

Amelanchier canadensis
Cotoneaster franchettii
Pittosporum tenuifolium
Viburnum tinus
Viburnum davidii
Cistus Silver pink
Stephanandra incisa cnispa
Hebe Gauntlettii
Lavandula Hidcote
Escallonia rubra Woodside
Deutzia Rosealind
Potentilla Sunset
Potentilla recta Warrenii
Phlomis italica

Native Hedge
Acer Campestre Field Maple
Corylus avellana Hazel
Crataegus monogyna Hawthorn
Ilex Aquifolium Holly
Viburnum lantana Wayfaring tree
Planted in a staggered row at 4 per linear metre

Elizabeth A. Ford
Landscape Architects
31 The Mallards
Langstone
Havant
Hampshire PO9 1SS
e-mail:lizford@landscape-architects.net
Tel: 02392 711970
Fax: 02392 711971

Project: Hayling Rise

Drawing: Landscape Proposals

Drawing no: AR/Hs/108.1-A

Scale: 1:150 @A1

Drawn by: EAF

Date: 14th january, 2011