Notes:

1. Cross Section A-A and B-B shown on Dwg.No. 1819/156041/P3
2. Acoustic fence to be installed to the south of No.20 Orchard Close property boundary. Timber Close Boarded 2.4m in height.

Change of Use from former Tennis Court to 3G Football Pitch. To comprise of;
- 4.2m High Rebound Fencing
- 6No. 8m High Floodlight Columns
- Top Netting to prevent balls going over the fence
- Central Curtain to split the larger pitch into two small pitches
- 3G Pitch Surface finished level to be same as existing

Existing Tennis Court to be reconstructed. To comprise of:
- Reconstruction of existing court. Surface finished level to be same as existing level.
- Replacement of existing fencing to the same height.
- Separating fence between 3G and Tennis courts to be double sided to match the facilities fence heights.
- Installation of new lining and nets, providing the same number of courts to the same layout.

Closed School

Orchard Close

20

Wooded Area

Locations of proposed Floodlight Columns

30m of 2.4m high acoustic fence

Existing Play Area

Existing MUGA

Proposed 3G Pitch

Reconstructed Tennis Courts

Existing Cricket Nets

Existing 2.8m high chain link fencing to be replaced with 4.2m high green weld mesh rebound fencing to all four sides

Locations of proposed Floodlight Columns

Existing 2.8m high chain link fencing to be replaced with 2.8m high green weld mesh fencing to three sides (northern, eastern & southern)

Southwick Recreation Ground

-5 0 5 10 15 20 25
Metres

Reproduced by permission of Ordnance Survey on behalf of HMSO. ©Crown Copyright and database right (2017). Ordnance Survey 100024321 & 100018824

	Description	By	Date
A	Acoustic fencing extended to 30m	MAP	07/06/19

AMENDMENTS

ADUR & WORTHING
COUNCILS
ENGINEERING SERVICES
TOWN HALL, CHAPEL ROAD
WORTHING BN11 1HA
TEL: 01903 239999
www.adur-worthing.gov.uk
engineers@adur-worthing.gov.uk

Southwick Leisure Centre Tennis Court Regeneration

BLOCK PLAN

Scale:	1:500@A2	Date:	Jan 2019
Drawn by:	RJB	Checked by:	KA
Drawing No:	1819/156041/P2		A