

Proposed South Elevation



Proposed East Elevation

Materials

Render - Colour: Creamy Avocado

Render - Parex G00 Natural White (or equal approved) with Monorex smooth textured finish

Cedral Cladding - Ship lapped cladding (Grey Brown C03)

Material Specifications:

Brickwork below Ground Floor Level - 65mm Red Class B Engineering Brick
Roof Finish - Sarnafil Single Ply Membrane
Windows - Dark grey foil wrapped U-PVC flush fitting casement windows
Entrance Doors - Powder coated aluminium
Fascias and Soffits: Powder coated aluminium (colour - dark grey)
Rainwater Goods - Black U-PVC deep capacity gutter and downpipes
Balconies - 1800mm high fully glazed balconies
Balcony Steelwork - mitred corner junctions
Balcony post - Steel columns clad with hardwood

Rev	Date	Revision Description	Drawn By	Approved By

ADG ARCHITECTS
6 Pioneer Court, Darlington, DL1 4WD
t: 01325 464 111
e: studio@adgarchitects.co.uk
w: www.adgarchitects.co.uk

Client: Caring Homes

Project Information: 75 Bed Care Home, The Priory, Worthing

Drawing Title: South and East Elevation

A1 Scale	A3 Scale
1:100	1:200

Job Number	Drawing Number	Revision
H.13.09	(21) 1	U

Drawing Issue: PLANNING

© Copyright 2017 ADG Architects Ltd