



Appendix F - Commercial Link Elemental Breakdown

Item	SERIES 1300 - Road Lighting Columns and Brackets, CCTV Masts and Cantilever Masts	Qty.	Unit	Rate	Total
	<u>Road Lighting Columns</u>				
A	Road lighting columns (taken every 30m, alternating sides of carriageway), 6m high tubular steel with LED lantern.	17	nr	£ 2,500.00	42,500.00
Series 1300 Total Carried to Summary					£ 42,500.00



Appendix F - Commercial Link Elemental Breakdown

Item	SERIES 1400 - Electrical Work for Road Lighting and Traffic Signs	Qty.	Unit	Rate	Total
	<u>Electrical Work for Lighting</u>				
A	Excavate trench for LV supply to streetlighting columns including sand bed and surround, ductwork and backfill to formation.	501	m	£ 40.00	£ 20,040.00
B	Excavate trench for LV supply to streetlighting columns including concrete bed and surround, ductwork and backfill to formation - Road Crossings.	84	m	£ 60.00	£ 5,040.00
Series 1400 Total Carried to Summary					£ 25,080.00



Appendix F - Commercial Link Elemental Breakdown

Item	SERIES 3000 - Landscape and Ecology	Qty.	Unit	Rate	Total
	<u>Trees</u>				
A	Included Elsewhere		nr		Incl.
	<u>Grass Seeding</u>				
B	Included Elsewhere		m²		Incl.
Series 3000 Total Carried to Summary					£ -